

Umed- Maharashtra State Rural Livelihoods Mission

उमेद -महाराष्ट्र राज्य ग्रामीण जीवनोन्नती अभियान

राज्य अभियान व्यवस्थापन कक्ष,
सिडको भवन, ५ वा मजला (दक्षिण कक्ष)
सी.बी.डी.बेलापूर, नवी मुंबई.
पिनकोड -४००६१४
दुरध्वनी -०२२-२७५६२५५२/५४

State Mission Management Unit
CIDCO Bhavan, 5th Floor (South Wing)
CBD Belapur, Navi Mumbai
Pincode : 400614
Phone No : 022-27562552/54

MSRLM/SMMU /GVB/Electric Panel work/

/2019

Date: - 30 /04 /2019

To,

M/s

.....

Subject: - Request for Quotation (RFQ) for Dismantling & re-erection of HT,LT &APFC panel at Gram Vikas Bhavan, Kharghar, Navi Mumbai.

Dear Sir,

- 1) Rural Development Department and Panchayat Raj Department, Government of Maharashtra has developed 'Gramvikas Bhavan' on plot no 76(A) in sector -21 at Kharghar, Navi Mumbai for organizing various seminars, workshops, trainings and meetings and providing residential facilities for the members of the Panchayat Raj Institutions coming to Mumbai for official work. The Panchayat Raj system in Maharashtra is being strengthened rapidly and more than 3 lakhs representatives are working towards the welfare of the rural population. To develop the skills of the representatives, the establishment of 'Gramvikas Bhavan' is a very vital and welcome step. The main objectives of this project include setting up of training centre for the members of the Panchayat Raj Institutions, providing facilities for exhibition and sales for Self Help Groups (SHGs), providing residential facilities for the members of the Panchayat Raj Institutions, creating platform for holding workshops and seminars to conduct poverty eradication programmes etc.
- 2) The Chief Executive Office of Maharashtra State Rural Livelihood Mission (MSRLM) on behalf of Rural development department, Government of Maharashtra invites quotation for Dismantling & re-erection of HT,LT &APFC panel at Gram Vikas Bhavan, Kharghar, Navi Mumbai.
- 3) Detailed scope of work:

Sr.No.	Item description	Unit	Qty
1	Dismantling of HT panel, LT panel & APFC panel	Nos	3
2	Dismantling of connected cables of all sizes 40 nos	Nos	40
3	Providing, erecting and fixing of iron fabrication work stand of 75 mm x 75 mm x 10 mm thick for HT panel, LT panel & APFC panel for increasing height upto 1.40 mtrs from ground level	Kg	700
4	Loading, lifting & re-erection of HT panel, LT Panel & APFC panel on the height increased iron frame	Nos	3
5	Providing, laying, fixing, connecting & testing of cable terminal kit for all size cables with suitable glands and lugs (for all short cables while lifting the panel high)	Nos	30
6	Rewinding of 3 Phase 7.5 HP water pump	Nos	3

- 4) **Qualification criteria:**

- a) The bidder should be government registered electrical contractor
- b) GST Registration.
- c) PAN card

5) Quotation Price:

- a. The quoted rates shall inclusive of required material and labour cost.
- b. The rates quoted by the agency shall be fixed for the duration of contract and in case of award shall not be subject to adjustment on any account.

6) Evaluation of Quotations: -

- a. Purchaser shall award the contract to the service provider whose offer/quote has been determined to be the lowest evaluated lowest cost
- b. GST in connection with the services will not be taken into account in evaluation.
- c. Evaluation shall be done for all the items together

7) Terms and Conditions :

- a. Each bidder shall submit only one quotation.
- b. Bidder shall not contract other bidder in matter relating to this Quotation.
- c. Conditional quotations which are not in line with this request for quotation shall be treated as non-responsive.
- d. Quotations must be submitted as per the attached format in a sealed envelope. Quotation in any other format and by any other means will not be accepted for evaluation.

8) Award of contract: -

- e. The SMMU-MSRLM will award the contract to the bidder whose quotation has been determined to be substantially responsive and who has offered the lowest evaluated quotation price.

9) Place of work and work completion period:

Place of work is Gramvikas Bhavan, plot no 76(A) in sector -21 at Kharghar, Navi Mumbai. Work should be completed within one week from the date of receipt of work order

10) Liquidated Damages:

The liquidated damage shall be 1.0% of per week for delay in completion of work subject to maximum 10% computed on the delivery delayed.

11) Quotation Submission:-

- a. Each bidder shall submit only one quotation in a sealed envelope boldly superscript as "Quotation for repairing of earthing work.
- b. You are requested to provide your offer latest by 11.00 AM hours on **08 /05 /2019** to above mentioned office address.

12) Opening of Quotation: -

Quotations will be opened in the presence of bidders representatives and SMMU-MSRLM representatives who choose to attend at Maharashtra State Rural Livelihood Mission, 5th Floor ,CIDCO Bhavan South wing ,CBD Belapur, Navi Mumbai -400614 on **08 /05 /2019 @ 11.30 AM.**

13) Payment:

The payment will be made within one week from the date of submission of tax invoice along with the completion report certified by the Gram Vikas Bhavan authority. Applicable GST will be paid upon submission of tax invoice.

Sd
R.Vimala IAS
Chief Executive Officer
Maharashtra State Rural Livelihoods Mission

QUOTATION FORMAT
(ON THE LETTER HEAD OF SUPPLIER)

To
Chief Executive Officer
Maharashtra State Rural Livelihoods Mission,
5th Floor, CIDCO Bhavan South wing
CBD Belapur, Navi Mumbai -400614

Date:- _____

Sub: - Regarding submission of quotation for Request for Quotation (RFQ) for Dismantling & re-erection of HT,LT &APFC panel at Gram Vikas Bhavan, Kharghar, Navi Mumbai.

Ref: Your quotation request letter no. MSRLM/SMMU /GVB/Electric Panel work/ /2019 dated 30/04/2019

Dear Sir,

As per your requirement, we are glad to submit you our most reasonable and competitive rates asunder

Sr. No.	Item description	Unit	Qty	Rate /unit in Rs.	Total amount without GST in Rs.
1	Dismantling of HT panel, LT panel & APFC panel	Nos	3		
2	Dismantling of connected cables of all sizes	Nos	40		
3	Providing, erecting and fixing of iron fabrication work stand of 75 mm x 75 mm x 10 mm thick for HT panel, LT panel & APFC panel for increasing height upto 1.40 mtrs from ground level	Kg	700		
4	Loading, lifting & re-erecting of HT panel, LT Panel & APFC panel on the height increased iron frame	Nos	3		
5	Providing, laying, fixing, connecting & testing of cable terminal kit for all size cables with suitable glands and lugs (for all short cables while lifting the panel high)	Nos	30		
6	Rewinding of 3 Phase 7.5 HP water pump	Nos	3		
	Total Amount without GST				

We agree to provide above mentioned work in accordance with the terms and condition and technical specifications mentioned in the invitation for quotation.

We hereby certify that we have taken steps to ensure that no person acting for us or on behalf will engage in bribery or collusive agreements with competition.

Name :-

Address :-

Contact no. :-

Signature of the supplier with stamp